

Incorrect Stair Storage on Site Costs you Time and Money



The Effects of Poor Storage

- ✘ May result in the stair being declared unfit for use
- ✘ Increases the risk of a poor-quality finish
- ✘ Replacement parts and labour, costing us all time and money
- ✘ Higher customer complaints and call backs
- ✘ Low NHBC CQR scores

Important Storage Recommendations



- ✓ Minimise storage on site by planning your Call-Offs and Deliveries to be close to the time when it will be installed.
- ✓ Store 1st fix Stairs in a designated container, or a dry garage/property, off the floor on bearers, with the wall string at the bottom.
- ✓ It is important to store Stair Components in a clean, well ventilated, water-tight area protected from damp and direct sunlight.
- ✓ Store 2nd fix Balustrades and Stair Parts in a designated container with shelving to hold loose Stair Parts and cantilever brackets to suspend Balustrades.
- ✓ Store in the correct order in line with build requirements.

For further guidance download the BWF installation guide

<https://www.bwf.org.uk/wp-content/uploads/bwf-stair-scheme-installation-guide-for-web.pdf>

Don't Forget To Download Our App

To Find Everything You Need For A Fully Integrated Solution Download Our App

